400.

BANGALORE DIVISION.

ADVERTISEMENT.

The 5th December 1889.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 6th January 1890, for constructing a Revenue Survey Office at Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1891.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 11 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. (100) one hundred in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing a Revenue Survey Office at Bangalore"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within 8 days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Approximate quantity of estimate for constructing a Revenue Survey Office at Bangalore.

Items of Work.	Quantity.	Per.	Rate.	Cost.	Total.
Earthwork excavation for foundation ..	906	C. Yd.			
Stone in chunam foundat on basement ..	16,290	..			
Brick in chunam superstructure ..	26,608	..			
Do archwork semi-circular ..	2,430	..			
Do segmental	513	..			
Plastering with chunam	469·84	Sqr.			
Pointing with chunam ..	17·10	..			
Whitewashing	196·90	..			
Color washing	272·94	..			
Cornice (1½ feet projection)	810	R. Ft.			
Do 1 foot do ..	320	..			
Do round head of piers ..	208	..			
String course around windows ..	1,044	..			
Flooring with concrete	84·54	Sqr.			
Terrace roofing	217·74	..			
Wood work (teak)	2,062	C. Ft.			
Stone slabs for steps .. .	128	S. Ft.			
Doors (excluding frames)	832	..			
Windows do	1,120	..			
Attic windows	336	..			
Glazed semi-circular fan lights over doors ..	416	..			
Bamboo matting	71·13	Sqr.			
Wood oiling	1	Item.			
Zink spouts	1	..			

R. T. SCALDWELL,
Executive Engineer.

CIVIL AND MILITARY STATION, BANGALORE.

IN THE COURT OF THE CIVIL JUDGE.

Mis. Application No. 387 *of* 1889.

1. Ramaiya, 2. Krishnaiya, 3. Narasimhaiya, 4. Pannelam Subba Sastri, 5. Nandula Ramachandraiya, 6. C. N. Murugesa Pille .. .. .. *Applicants.*

In the matter of the estate of the late Codecanda Lakshmipati Sastri .. *Deceased.*

Whereas 1. Ramaiya, 2. Krishnaiya, 3. Narasimhaiya, 4. Pannelam Subba Sastri, 5. Nandula Ramachandraiya, 6. C. N. Murugesa Pille, executors and trustees to the estate of the deceased above named, have applied to this Court for probate to the last Will of the said deceased who died at Bangalore on the 7th day of November 1887, at 8-30 A. M., and Wednesday the 18th day of December 1889 at 11 A. M. has been fixed for the hearing of the application.

All persons claiming to have any interest in the estate of the deceased are hereby called upon to come and see the proceedings on or before the said 18th day of December 1889.

Given under my hand and the seal of the Court this 3rd day of December 1889.

W. HILL,
Civil Judge.